

## 2015 SUDAS Supplement Revisions

Section 1020 – 1.01 Qualification of the bidders revised to match City contract documents  
1.05 Interpretation of the contract documents revised to match City contract documents  
1.08 Taxes revised to match City contract documents  
1.11 Irregular and nonresponsive proposal revised to match City contract documents  
1.13 Withdrawal of bids revised to match City contract documents  
1.15 Limitation on withdrawal of proposals after opening of proposals removed to match City contract documents  
1.16 Nondiscrimination and affirmative action added to match City contract documents  
1.17 Jurisdiction added to match City contract documents  
1.18 Payment not acceptance of defective work added to match City contract documents  
1.19 Bidders status form added to match City contract documents  
1.20 Governing law added to match City contract documents  
1.21 Certificates of insurance added to match City contract documents

Section 1050 – 1.12 Specify items to be salvaged and delivered to City

Section 1070 – Part 3, 3.02 Automobile liability insurance requirements increased to \$2,000,000.

Section 1080 – 1.01 Subletting or assignment of contracts altered to allow for variation in work percentage requirement for prime if specified in special provisions

Section 5010 – 2.05 A. Polyethylene wrap on DIP is only required if the corrosive soil testing determines it is necessary  
2.05 B. Tracer wire continuity test shall be completed by 3<sup>rd</sup> party prior to project acceptance  
3.10 D. Table location correction  
3.10 E. Stop boxes to be placed outside of paving  
Figure SC 5010.201 Thrust block added to the capped end of the new tee on the existing water main

Section 5020 – 2.02 C. 6. C. 2. Steamer threads removed as Storz nozzles are now required instead  
2.03 B. 3. Removed word paved  
Figure SC 5020.301 Altered to show the valve anchored to the tee

Section 6010 – Removed 2.11 A.2. Internal Rubber Seal: Must be installed on all manholes regardless of sewer type  
Added 2.19 Additional Materials for Storm Sewer Manholes – A. Internal Rubber Seal: Must be installed on all storm sewer manholes. Refer to SUDAS 6010 2.11 A. for specifications

Section 7010 – 2.02 A. Added quartzite mix.

Section 9030 – Part 1, 1.08 Revised payments on plants to 70% at time of installation & 30% at time of acceptance  
Part 3, 3.12 A & B Revised establishment period to end at time of acceptance and specify a 2 year warranty period

Section 9090 – Removed project sign requirements